Pre-Measurements

Name of Work : - Improvements to roads and drains at Hegdenagar and surrounding area in Ward No 06 Vyatarayanapura sub division.

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks
	MH-3			-1			0.64		0.25	-0.16	(-)
	MH-4			-1			0.64		0.25	-0.16	(-)
	MH-5			-1			0.64		0.25	-0.16	(-)
	6th Cross Road (GKVK Double Rd to RKH 2nd Mn Rd)										
	0.00	3.00		1	3.00	1.20	1.50	1.35	0.25	1.01	
	3.00	8.00		1	5.00	1.50	2.30	1.90	0.25	2.38	
	8.00	8.50		1	0.50	2.30	1.30	1.80	0.25	0.23	
	8.50	16.00		1	7.50	1.30	3.20	2.25	0.25	4.22	
	16.00	16.50		1	0.50	3.20	1.25	2.23	0.25	0.28	
	16.50	20.00		1	3.50	1.25	5.25	3.25	0.25	2.84	
	20.00	27.00		1	7.00	5.25	1.50	3.38	0.25	5.91	
	27.00	48.00		1	21.00	1.50	2.80	2.15	0.25	11.29	
	48.00	56.00		1	8.00	2.80	1.40	2.10	0.25	4.20	
	56.00	60.00		1	4.00	1.40	1.20	1.30	0.25	1.30	
	60.00	74.00		1	14.00	1.20	2.80	2.00	0.25	7.00	
	74.00	80.00		1	6.00	2.80	3.50	3.15	0.25	4.73	
	80.00	87.00		1	7.00	3.50	1.40	2.45	0.25	4.29	
	87.00	95.00		1	8.00	1.40	1.20	1.30	0.25	2.60	
	95.00	96.00		1	1.00	1.20	4.40	2.80	0.25	0.70	
	96.00	125.00		1	29.00	4.40	2.10	3.25	0.25	23.56	
	125.00	130.00		1	5.00	2.10	2.50	2.30	0.25	2.88	
	130.00	135.00		1	5.00	2.50	1.20	1.85	0.25	2.31	
	135.00	143.00		1	8.00	1.20	4.50	2.85	0.25	5.70	
	143.00	148.00		1	5.00	4.50	1.30	2.90	0.25	3.63	
	148.00	153.00		1	5.00	1.30	2.20	1.75	0.25	2.19	
	153.00	160.00		1	7.00	2.20	1.50	1.85	0.25	3.24	
	160.00	166.00		1	6.00	1.50	2.20	1.85	0.25	2.78	
	166.00	174.00		1	8.00	2.20	2.80	2.50	0.25	5.00	
	174.00	182.00		1	8.00	2.80	2.60	2.70	0.25	5.40	
	182.00	192.00		1	10.00	2.60	2.20	2.40	0.25	6.00	
	192.00	205.00		1	13.00	2.20	3.50	2.85	0.25	9.26	
	205.00	214.00		1	9.00	3.50	3.20	3.35	0.25	7.54	
	214.00	221.50		1	7.50	3.20	1.80	2.50	0.25	4.69	
	Manhole Deductions										
	MH-1			-1				0.64	0.25	-0.16	(-)
	MH-2			-1				0.64	0.25	-0.16	(-)
	MH-3			-1				0.64	0.25	-0.16	(-)
	MH-4			-1				0.64	0.25	-0.16	(-)
	MH-5			-1				0.64	0.25	-0.16	(-)
	MH-6			-1				0.64	0.25	-0.16	(-)
	MH-7			-1				0.64	0.25	-0.16	(-)

135.53

Tejus Consultants

Assistant Engineer

Assistant Executive Engineer

Scanned with CamScanner

Pre-Measurements

Name of Work : - Improvements to roads and drains at Hegdenagar and surrounding area in Ward No 06 Byatarayanapura sub division.

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks
	BDS Layout 2nd 'A' c/s Rd(Dr.Shivarama Karanth nagar Mn to GKVK Double Mn Rd)										
	0.00	2.00		1	2.00	6.00	5.50	5.75	0.25	2.88	
	2.00	23.00		1	21.00	5.50	5.50	5.50	0.25	28.88	
	23.00	32.00		1	9.00	5.50	5.50	5.50	0.25	12.38	
	32.00	50.00		1	18.00	5.50	5.60	5.55	0.25	24.98	
	50.00	57.00		1	7.00	5.60	5.70	5.65	0.25	9.89	
	57.00	63.00		1	6.00	5.70	3.00	4.35	0.25	6.53	
	63.00	72.00		1	9.00	3.00	2.50	2.75	0.25	6.19	
	BDS Layout 2nd c/s Rd(Dr.Shivarama Karanth ngar Mn to Amanthrana Party Hall)										
	0.00	4.00		1	4.00	7.00	6.50	6.75	0.25	6.75	
	4.00	20.00		1	16.00	6.50	6.50	6.50	0.25	26.00	
	20.00	40.00		1	20.00	6.50	6.70	6.60	0.25	33.00	
	40.00	56.00		1	16.00	6.70	6.60	6.65	0.25	26.60	
	56.00	62.00		1	6.00	6.60	2.80	4.70	0.25	7.05	
	62.00	83.70		1	21.70	2.80	2.50	2.65	0.25	14.38	
	83.70	85.00		0	1.30	0.00	0.00	0.00	0.25	0.00	
	Manhole Deductions										
	MH-1			-1				0.64	0.25	-0.16	
	MH-2			-1				0.64	0.25	-0.16	
	BDS Layout 1st c/s Rd(Dr.Shivarama Karanth ngar Mn to GKVK Double Rd)										
	0.00	24.00		1	24.00	2.40	3.00	2.70	0.25	16.20	
	24.00	40.00		1	16.00	3.00	3.80	3.40	0.25	13.60	
	40.00	53.00		1	13.00	3.80	3.80	3.80	0.25	12.35	
	53.00	64.00		1	11.00	3.80	2.80	3.30	0.25	9.08	
	64.00	80.00		1	16.00	2.80	2.60	2.70	0.25	10.80	
	80.00	100.50		1	20.50	2.60	3.50	3.05	0.25	15.63	
	100.50	102.20		1	1.70	3.50	3.50	3.50	0.25	1.49	
								Total Quantity		1472.27	Cum

284.30

Tejus Consultants

Assistant Engineer

Assistant Executive Engineer

Scanned with CamScanner

BRUHAT BANGALORE MAHANAGARA PALIKE
BYTARAYANPURA DIVISION

Name of Work: Package 2 Consists of 3 Works of Rs.1100.00 Lakhs

3. Improvements to roads and drains at Hegdenagar and surrounding area in Ward No 06 Byatarayanapura sub division.

DETAILED-MEASUREMENT

SECOND & PART BILL

TEJUS CONSULTANTS
CONSULTING ENGINEERS AND DESIGNERS
No.58 MIG, 6th Cross, 3rd Main
1st Stage, Basaveshwaranagar
Bangalore-560079
☎ 080 - 23287532
email: tejusconsultants@gmail.com

Scanned with CamScanner

BRUHAT BANGALORE MAHANAGARA PALIKE

BYATARAYANAPURA SUB DIVISION

Bill No :Second and Part Bill

Name of Agency :- Benaka Developers & Project Pvt.Ltd.

Name of Work : - Improvements to roads and drains at Hegdenagar and surrounding area in Ward No 06 Byatarayanapura sub division.

BOQ Item No	Description / Chainage	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
1	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(P.No-143 &136 ,I No-19.1&17.4& 17.1) 5km lead= 57+2.0x1.28x5=69.80											
	Measurements recorded on											
	Qty vide Pre measurement sheet page no . 01 of 8							**Total Quantity**	734.18	cum	234.00	1,71,799.00
2	Removing and refixing stone slabs of drains and pointing in CM (1:3) (P.No.27, I.No.5.33 of PW, P&IWTD SR 2018-19)											
	Cover Slab											
	Shirdi Sai Rathan Layout											
	2nd Cross Rd											
	LHS											
	106.00	110.30	L/S	1	4.30			1.20	5.16	1.2 bs		
	110.30	121.20	L/S	1	10.90			0.90	9.81	0.9 bs		
	RHS											
	30.00	43.50	R/S	1	13.50			1.20	16.20	1.2 bs		
	43.50	47.50	R/S	1	4.00			0.90	3.60	0.9 bs		
	Connected to 2nd A ,B and 1st Cross Road											
	LHS											
	58.50	67.50	L/S	1	16.00			0.90	14.40	0.9 bs		
	67.50	71.20	L/S	1	3.70			1.20	4.44	1.2 bs		
	78.00	90.80	L/S	1	12.80			0.90	11.52	0.9 bs		
	1st Cross Road											
	LHS											
	123.00	132.00	L/S	1	9.00			0.90	8.10	0.9 bs		
	RHS											
	111.70	123.00	R/S	1	11.30			0.90	10.17	0.9 bs		
	123.00	132.00	R/S	1	9.00			0.90	8.10	0.9 bs		
	132.00	136.60	R/S	1	4.60			0.90	4.14	0.9 bs		
	Hegdenagar											
	1st Cross Road (GKVK Double Rd to RKH 2nd Mn Rd)											
	LHS											
	41.00	49.00	L/S	1	8.00			0.90	7.20	0.9 BS slab		
	212.00	221.00	L/S	1	9.00			0.90	8.10	0.9 BS slab		
	2nd Cross Road (GKVK Double Rd to RKH 2nd Mn Rd)											
	LHS											
	25.00	30.00	L/S	1	5.00			0.90	4.50	0.9 BS slab		
	3rd Cross Road (GKVK Double Rd to RKH 2nd Mn Rd)											
	RHS											
	67.50	72.50	R/S	1	5.00			1.20	6.00	1.2 BS		
	5th Cross Road (GKVK Double Rd to RKH 2nd Mn Rd)											

CHECKED 19/11/2020

121.44

Tejus Consultants

Assistant Engineer

Assistant Executive Engineer

Scanned with CamScanner

Name of Work : - Improvements to roads and drains at Hegdenagar and surrounding area in Ward No 06 Byatarayanapura sub division.

BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	Chainage												
	LHS												
	26.00	30.00	L/S	1	4.00			1.20		4.80	1.2 BS		
	Apoorva Enclave												
	Culvert Desilt												
	254.50	256.30		1	9.50			1.50		14.25	1.5 BS Slab		
										19.05			
								Total Quantity		140.49	Sqm	112.00	15,735.00
3	Removing and resetting of footpath slab (P.No.270, I.No.37.56 of PW, P&IWTD SR 2018-19)												
	Hegdenagar												
	1st Cross Road (GKVK Double Rd to RKH 2nd Mn Rd)												
	LHS												
	0.00	15.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	15.00	30.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	30.00	41.00	L/S	1	11.00			0.90		9.90	0.9 PCS		
	49.00	60.00	L/S	1	11.00			0.90		9.90	0.9 PCS		
	60.00	75.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	75.00	90.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	90.00	105.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	105.00	120.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	120.00	135.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	135.00	156.00	L/S	1	21.00			0.90		18.90	0.9 PCS		
	174.00	193.00	L/S	1	19.00			0.90		17.10	0.9 PCS		
	202.00	212.00	L/S	1	10.00			0.90		9.00	0.9 PCS		
	RHS												
	0.00	15.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	15.00	30.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	30.00	45.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	45.00	60.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	60.00	75.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	75.00	90.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	90.00	105.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	105.00	120.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	120.00	135.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	135.00	150.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	150.00	165.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	165.00	180.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	180.00	195.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	195.00	210.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	210.00	225.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	225.00	240.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	240.00	249.00	R/S	1	9.00			0.90		8.10	0.9 PCS		
	2nd Cross Road (GKVK Double Rd to RKH 2nd Mn Rd)												
	LHS												
	2.00	14.00	L/S	1	12.00			0.90		10.80	0.9 PCS		
	30.00	45.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	45.00	60.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	60.00	75.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	75.00	90.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	90.00	105.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	105.00	128.00	L/S	1	23.00			0.90		20.70	0.9 PCS		
	141.00	150.00	L/S	1	9.00			0.90		8.10	0.9 PCS		
	150.00	165.00	L/S	1	15.00			0.90		13.50	0.9 PCS		

Tejus Consultants

Assistant Engineer

Assistant Executive Engineer

Scanned with CamScanner

Name of Work : - Improvements to roads and drains at Hegdenagar and surrounding area in Ward No 06 Byatarayanapura sub division.

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	165.00	180.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	180.00	195.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	195.00	210.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	237.00	246.00	L/S	1	9.00			0.90		8.10	0.9 PCS		
	RHS												
	2.00	15.00	R/S	1	13.00			0.90		11.70	0.9 PCS		
	15.00	30.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	65.00	74.00	R/S	1	9.00			0.90		8.10	0.9 PCS		
	87.00	109.00	R/S	1	22.00			0.90		19.80	0.9 PCS		
	114.00	130.00	R/S	1	16.00			0.90		14.40	0.9 PCS		
	130.00	155.50	R/S	1	25.50			0.90		22.95	0.9 PCS		
	175.00	190.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	190.00	205.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	205.00	220.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	220.00	239.00	R/S	1	19.00			0.90		17.10	0.9 PCS		
	3rd Cross Road (GKVK Double Rd to RKH 2nd Mn Rd)												
	LHS												
	2.00	15.00	L/S	1	13.00			0.90		11.70	0.9 PCS		
	15.00	30.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	30.00	46.00	L/S	1	16.00			0.90		14.40	0.9 PCS		
	64.70	90.00	L/S	1	25.30			0.90		22.77	0.9 PCS		
	108.00	115.00	L/S	1	7.00			0.90		6.30	0.9 PCS		
	115.00	130.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	130.00	145.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	145.00	160.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	160.00	175.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	175.00	195.00	L/S	1	20.00			0.90		18.00	0.9 PCS		
	225.00	241.00	L/S	1	16.00			0.90		14.40	0.9 PCS		
	RHS												
	2.00	15.00	R/S	1	13.00			0.90		11.70	0.9 PCS		
	15.00	30.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	30.00	45.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	45.00	67.50	R/S	1	22.50			0.90		20.25	0.9 PCS		
	84.00	107.00	R/S	1	23.00			0.90		20.70	0.9 PCS		
	120.00	133.00	R/S	1	13.00			0.90		11.70	0.9 PCS		
	154.00	167.00	R/S	1	13.00			0.90		11.70	0.9 PCS		
	179.80	195.00	R/S	1	15.20			0.90		13.68	0.9 PCS		
	195.00	212.00	R/S	1	17.00			0.90		15.30	0.9 PCS		
	231.00	241.00	R/S	1	10.00			0.90		9.00	0.9 PCS		
	5th Cross Road (GKVK Double Rd to RKH 2nd Mn Rd)												
	LHS												
	0.00	26.00	L/S	1	26.00			0.90		23.40	0.9 PCS		
	43.60	60.00	L/S	1	16.40			0.90		14.76	0.9 PCS		
	60.00	75.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	75.00	90.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	90.00	105.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	105.00	120.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	120.00	135.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	135.00	150.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	150.00	165.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	165.00	180.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	180.00	199.00	L/S	1	19.00			0.90		17.10	0.9 PCS		
	210.00	227.50	L/S	1	17.50			0.90		15.75	0.9 PCS		

CPC 23.2.22 11/11/2022

Tejus Consultants

BENAKA DEVELOPERS AND ARCHITECTS PVT. LTD. BANGALORE

Assistant Engineer

ಸಹಾಯಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ಉಪ ವಿಭಾಗ

Assistant Executive Engineer
ಬ್ಯಾಟರಾಯನಪುರ ಉಪ ವಿಭಾಗ

Scanned with CamScanner

Name of Work : - Improvements to roads and drains at Hegdenagar and surrounding area in Ward No 06 Byatarayanapura sub division.

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	RHS												
	0.00	15.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	15.00	30.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	30.00	45.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	45.00	68.00	R/S	1	23.00			0.90		20.70	0.9 PCS		
	104.00	120.00	R/S	1	16.00			0.90		14.40	0.9 PCS		
	120.00	135.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	135.00	150.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	150.00	165.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	165.00	180.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	180.00	195.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	195.00	205.00	R/S	1	10.00			0.90		9.00	0.9 PCS		
	205.00	220.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	220.00	227.50	R/S	1	7.50			0.90		6.75	0.9 PCS		
											C/F C		
	6th Cross Road (GKVK Double Rd to RKH 2nd Mn Rd)												
	LHS												
	0.00	15.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	15.00	30.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	30.00	45.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	45.00	60.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	60.00	75.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	75.00	96.00	L/S	1	21.00			0.90		18.90	0.9 PCS		
	108.00	120.00	L/S	1	12.00			0.90		10.80	0.9 PCS		
	120.00	135.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	135.00	150.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	150.00	165.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	165.00	180.00	L/S	1	15.00			0.90		13.50	0.9 PCS		
	180.00	199.00	L/S	1	19.00			0.90		17.10	0.9 PCS		
	199.00	210.00	L/S	1	11.00			0.90		9.90	0.9 PCS		
	210.00	221.50	L/S	1	11.50			0.90		10.35	0.9 PCS		
	RHS												
	0.00	15.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	15.00	30.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	30.00	45.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	45.00	60.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	60.00	75.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	75.00	90.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	90.00	105.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	105.00	120.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	120.00	135.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	135.00	150.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	150.00	165.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	165.00	180.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	180.00	195.00	R/S	1	15.00			0.90		13.50	0.9 PCS		
	195.00	205.00	R/S	1	10.00			0.90		9.00	0.9 PCS		
	205.00	221.50	R/S	1	16.50			0.90		14.85	0.9 PCS	560.25	
								Total Quantity		**1736.01**	**Sqm**	**210.00**	**3,64,562.00**
6	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar & stone hammerd dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, HOM, curing complete as per specifications. KBS 5.1.13. cement mortar 1:6(P.No.255, I.No.3.4.8.2 of PW, P&IWTD S.R 2018-19)												

Measurements recorded on:

Tejus Consultants

Assistant Engineer

Assistant Executive Engineer

Scanned with CamScanner

Detailed Measurements

Name of Work : - Improvements to roads and drains at Hegdenagar and surrounding area in Ward No 06 Byatarayanapura sub Division.

BOQ Item No	Description / Chainage	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
												29330.00
	Qty vide Pre measurement sheet page no . 8							Total Quantity	5.77	Cum	4910.00	28,348.00
7	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, for coping. Including cost of all materials, labour, HOM, curing complete as per specifications.Specification No. KBS 4.1, 4.2(P.No 255, I.No.34.11 of PW,P&IWTD S.R 2018-19)											
Measurements recorded on												14394.00
	Qty vide Pre measurement sheet page no . 8							Total Quantity	2.55	Cum	5645.00	14,403.00
11	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge											
	New Culvert Slab		1	9.40			1.50		14.10			
								Total Quantity	14.10	Sqm	5201.00	73,334.00
12	KSRRB M300-14. Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications MORTH Specification MORTH Specification No.30?with 4km lead= (I No-19.14,P No-143)											
Measurements recorded on	9 of 15							Total Quantity	1766.72	Cum	60.00	1,06,003.00
13	KSRRB M400-17. Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications(P.No-155,I No-20.18)											
Measurements recorded on	15 of 21							Total Quantity	1472.27	Cum	1729.00	25,45,555.00
											Total Amount	33,19,739.00
											Add 12% GST	3,98,368.68
											Grand Amount	37,18,107.68

37,18,077.44

Tejus Consultants

Assistant Engineer

Assistant Executive Engineer

Scanned with CamScanner